

RFP 2024-25-002 Construction of a Multi-Purpose Facility

ADDENDUM #01

September 20, 2024

The following changes were made by the owner and are only provided on this addendum, not on original drawings.

Sheet C-0 – Concrete may be used in leu of asphalt

Sheet E-2 - Remove EUH-2

Sheet E-6 - Remove load from panel A circuit 27,29

Sheet P-2 - Remove backflow device

Sheet P-4 - Change NFWH to 12-in L x 1/2-in MIP Brass Anti-siphon Frost Resistant Half Turn Sillcock

General Notes

15. Remove trap primer
25. Pex may be used in leu of copper
26. Sanitary Sewer to be PVC Schedule 40 DWV